KRŠKO NUCLEAR POWER PLANT

10

Mining Knotherster

0

KRŠKO NUCLEAR POWER PLANT


2



The Krško Nuclear Power Plant is equipped with the Westinghouse pressurised water reactor with the thermal power of 1994 MW. The plant is connected with the 400 kV transmission system to cover the needs of major consumers of the Republic of Slovenia and the Republic of Croatia. Following steam generators' and low pressure turbines' replacement, and power uprate, the plant output has increased to 696 MW net. The planned annual electric power production amounts to 5 TWh. This represents about 40 per cent of all the electricity produced in Slovenia.

The Krško Nuclear Power Plant is located on the left bank of the Sava River in the industrial zone of Krško town. The access to the plant is provided by means of the industrial road linked to the regional road Krško - Brežice. The plant also has an industrial railway line, which connects it with the Krško Railway Station.

The mission and responsibility of the plant are safe and stable plant operation, competitive electricity production and favourable public opinion.



4 ERECTION OF THE KRŠKO NUCLEAR POWER PLANT

After the Krško basin had been selected as a candidate site for Nuclear Power Plant, the working group of the Republic of Slovenia Business Association for Electric Power Resources in collaboration with Slovene Electric Power Utilities and research institutes carried out first researches during the period from 1964 to 1969.

Following the proposal given by Slovene and Croatian electric power utilities in 1970, the Governments of Slovenia and Croatia signed an agreement on joint construction of nuclear power plant to cover the increasing needs for electric power in both Republics

The decision to construct nuclear power plants was expedited by the fact that both Republics lacked conventional power resources. The investors of the plant were Savske elektrarne, Ljubljana and Elektroprivreda, Zagreb. Their Investment Team carried out preparatory works, officially invited tenders and selected the most auspicious one.

In August 1974 the two investors entered into a turnkey contract with the with the American company Westinghouse Electric Corporation for the supply of equipment and the construction of the 632 MW Nuclear Power Plant. So, the main contractor was Westinghouse; the designer was the American company Gilbert Associates Inc., while the works were entrusted to Slovene and Croation companies.

On 1 December 1974 Josip Broz Tito – the then President of the former Yugoslavia – laid the foundation stone for the Krško Nuclear Power Plant. Civil works were carried out by Gradis and Hidroelektra, and erection works by Hidromontaža and Đuro Đaković.

The Republic of Slovenia and the Republic of Croatia participated equally in providing financial resources.



STRUCTURES

6

All principle structures of the Nuclear Power Plant are located on a solid reinforced concrete platform, which is situated upon the Pliocene sandy-clay sediments of the Krško basin. The platform of the Krško basin forms solid and seismically safe foundation. The structures are designed and constructed to resist anticipated earthquakes in this area free from major damages.


The Reactor Building, where the Reactor Coolant System and Safety Systems are installed, consists of the inner cylindrical steel shell and the outer reinforced concrete shield building. The Containment Airlock is equipped with sealed passage chamber with double doors. Numerous piping and cable penetrations are double sealed. Adjacent to the Reactor Component Cooling Building, Fuel Handling Building, Diesel Generator Building and Turbine Building are located.

Cooling water and Essential Service Water intake structures are located on the Sava River bank above the Sava River dam, which maintains adequate water level. Cooling water discharge structure is below the Sava River dam. In addition, Cooling Towers of a draft multi-cell type are provided for cooling circulating water in case of low water flow of the Sava River.

Solid Waste Storage is located on the south-western side of the plant; administration building with workshops and the switchyard are located on the north side, at the plant entrance.




SCHEMATIC CROSS-SECTION OF THE PLANT





8




- 1. Steam Generators
- 2. Pressuriser
- **3.** Reactor Coolant Pumps
- 4. Reactor

Westinghouse pressurised water reactor with two cooling loops consists of the reactor vessel with its internals and head, two steam generators, two reactor coolant pumps, pressuriser, piping, valves, and of reactor auxiliary systems. Demineralised water serves as reactor coolant, neutron moderator and for dilution of boric acid solution. In the steam generator the reactor coolant gives up its heat to the feedwater on the secondary side of the steam generator to generate steam. Reactor coolant pressure is maintained by the pressuriser, which is supported by electrical heaters and water sprays, which are supplied with water from the cold legs of the reactor coolant.

Data necessary for reactor control and reactor protection is provided by measuring the neutron flux, reactor coolant temperature, flow rate, pressuriser water level and pressure detectors.

Reactor power is regulated by control rods. Control rod drive mechanism is fixed on the reactor head, while the absorber rods extend into the reactor core. Long-term core reactivity changes and core poisoning with fission products are compensated by means of boric acid concentration change in the reactor coolant.



REACTOR VESSEL

- 1. Control Rod Drive Mechanism
- 2. Reactor Vessel Head
- **3.** Upper Support Plate
- 4. Core Barrel
- 5. Outlet Nozzle
- 6. Upper Core Plate
- 7. Fuel Assemblies
- 8. Lower Core Plate
- 9. Support Plate Forging
- **10.** Thermal Sleeves
- 11. Control Rod Assembly Conduit
- 12. Control Rod Assembly Drive Shaft
- 13. Inlet Nozzle
- 14. Diffuser
- 15. In-core Nuclear Instrumentation Guide Thimbles

NUCLEAR FUEL ASSEMBLY

(1)

(2)

3

(4)

(5)

(6)

(7)


- 1. Control Rod Assembly
- 2. Top Nozzle
- 3. Control Rod Guide Thimble
- 4. Bottom Nozzle
- 5. Absorber Rod
- 6. Grid Assembly
- 7. Fuel Rod

The reactor core is composed of 121 fuel assemblies. Each fuel element consists of fuel rods, top and bottom nozzles, grid assemblies, control rod guide thimbles and instrumentation guide thimbles. Fuel rods contain ceramic uranium dioxide pellets welded into ZIRLO tubes. Uranium oxide fuel is shaped into sintered pellets and enriched with the uranium 235.

During outage – every 18 months – almost half of the fuel assemblies is replaced by fresh ones. Fresh fuel assemblies are kept in the Fresh Fuel Storage. Spent fuel elements are kept and cooled under water in the Spent Fuel Pit.


During refuelling fuel assemblies are removed from the reactor through flooded transfer canal penetrating the containment vessel into the Spent Fuel Pit. During the refuelling the reactor is open and the reactor cavity is flooded. The refuelling machine removes the spent fuel assemblies from the reactor core and replaces them with the fresh ones. Fuel assemblies remain in the rector core at least two fuel cycles.

NUCLEAR FUEL



FUNCTIONAL DIAGRAM

- Reactor
- 2. Reactor Coolant Pumps
- 3. Steam Generators
- 4. Pressuriser
- 5. High Pressure Turbine
- 6. Low Pressure Turbines
- 7. Generator
- 8. Moisture Separator
- 9. Reheater
- 10. Condensers
- 11. Condensate Pumps
- 12. Low Pressure Heater
- 13. Feedwater Pump
- 14. High Pressure Feedwater Heater
- 15. Circulating Water Pumps
- 16. Mechanical Draft Multi-cell Cooling Towers
- 17. Cooling Tower Circulating Pumps
- 18. Transformer



14


The steam generators generate saturated steam, which drives the turbine. In the double-flow high-pressure turbine the steam expands to 0.8 MPa. Then the steam flows through moisture separator and through reheater into double-flow low-pressure turbine where it expands to 5 kPa. After the steam is condensed in the condensers, the feedwater pumps return it through the heaters into the steam generators.

The power of the three-phase generator is 850 MVA, its cos fi 0.876, and the voltage 21 kV. The generator rotor is cooled with hydrogen and the stator is cooled with water. The exciter is brushless. When the Sava River flow exceeds 100 m³/s, the condensers are cooled by means of direct river water trough flow. In case of lower river flow such cooling is combined with cooling towers, so that at the lowest flow rates a small amount of water is drawn from the Sava River, while the remaining water is circulated by cooling water discharge into the Sava River. The Sava River temperature may increase for 3° C maximum and must not exceed 28° C in a mixing point.

The Krško Nuclear Power Plant is connected to the 400 kV transmission system through the 400 kV switchyard. Electric energy flows from the generator through two main transformers to the 400 kV switchyard. Then it continues through one transmission line towards Maribor and two transmission lines towards Ljubljana, through two transmission lines towards Zagreb and through buses to the distribution and transformer station – Krško TS 400/110 kV.

The plant is supplied either from its generator or 400 kV transmission system. In case of the 400 kV transmission system failure, the electric power is supplied through the 110 kV cable from the Krško TS 400/110 kV. The backup supply of electric power is assured from the Brestanica Gas-steam Power Plant, which is 7 km away from the Krško Nuclear Power Plant. The Brestanica Power Plant can cut-off all other consumers and supply the power only to the Krško Nuclear Power Plant.

In addition, the plant is provided with three diesel generators, each with rated power of 3500 kW, which serve as an independent emergency electric power source for essential plant systems and are able to respond in 10 seconds already.



ON LINE DIAGRAM

G	Generator
GT	Main Transformer
DG	Diesel Generator
-0.0-	Circuit Breaker
-0_1-	Disconnect Switch
M	Motor
\bigcirc	Unit Transformer
\mathcal{R}	Auxiliary Transformer
G, M, MD	Buses
DV	Transmission Line
GT, T, TD	Transformer
κv	Cable
RTP	Krško TS 400/110 kv
ТР	Transformer Bay

RADIOACTIVE WASTES AND ENVIRONMENTAL PROTECTION


During the Nuclear Power Plant operation gaseous, liquid and solid wastes are produced. The plant is provided with the Gaseous Waste Processing System which consists of two parallel closed loops with compressors and catalytic hydrogen recombiners and of six decay tanks for compressed fission gases. Four of the tanks are used during normal plant operation, while the remaining two are used during reactor shutdown. The capacity of the tanks is adequate for more than onemonth gaseous waste hold-up. Within this period the majority of the shortlived fission gases decay, while the remaining gases are released into the atmosphere under favourable meteorological conditions. Automatic radiation monitors in the ventilation duct prevent uncontrolled release when the radioactive gas concentration exceeds the permissible level.

Liquid radioactive wastes are purified in the Liquid Waste Treatment Facilities consisting of tanks, pumps, filters, the evaporator, and two demineralisers. The blow-down water from the steam generators is purified separately. The radioactivity of the water discharged into the Sava River is considerably below the maximum permissible concentration.

All solid radioactive wastes, generated during the plant operation, maintenance activities and servicing are collected in the Solid Waste Storage. Used ion exchangers, evaporator concentrates, used filters, and other contaminated solid wastes, as paper, towels, working clothes, laboratory equipment, and various tools are major solid wastes. Solid wastes are compressed and encapsulated into 208-litre steel casks. These casks are temporarily kept in the Solid Waste Storage within the plant area.

Modern Waste Treatment Facilities and continuous off-site radiological monitoring ensure that off-site radiation during the plant operation is less than 0.1 per cent of the dose received annually from natural background and artificial sources.

The offsite radiological monitoring is being carried out since 1974 already and comprises surveillance of 50 locations in local land environment. The following media are regularly monitored: air, waters, precipitation, suspended matter, deposits, biota of the Sava River and underground waters. Dose calculations are compared to natural external dose rate and atmospheric deposits from preoperational monitoring. All the measurements are being carried out during the plant operation as well.



71

32

38

CONTAINMENT

m

m

m MPa 0.357

(at) (3.62)

m 3.69

m 11.9

m 0.168

t 327

t 436



NUCLEAR POWER PLANT

Reactor Thermal Power	MW	1994
 Gross Electrical Output 	MW	727
 Net Electrical Output 	MW	696
 Engineering Minimum 	MW	32
 Heat Consumption 	kcal/kWh	2560
 Thermal Efficiency Factor 	%	36

• Thermal Efficiency Factor

	Height
-	neigni

- Inside Diameter
- Outside Diameter
- Steel Shell Test Pressure

REACTOR VESSEL

- Outside Diameter
- Height
- Wall Thickness
- Empty Vessel Weight
- Vessel Weight with Internals

REACTOR COOLANT

H ₂ O
I,BÔ,
[°] 2
9021
15.41
(157)
197
287
324
2
6.3
5.22

STEAM GENERATORS

STEAM GENERATORS			
 Material 	INCONEL	690 T T	
 Number of Steam Generators 		2	
 Steam Pressure at Steam 	MPa	6.5	
Generator Outlet	(at)	(63.5)	
 Steam Temperature at Steam 	°C	280	
Generator Outlet			
Feedwater Temperature at Steal	m °C	219	
Generator Inlet			
Total Steam Mass Flow		s 1088	
 Steam Generator Height 	m	20.6	
Steam Generator Weight	t	345	
Number of U-tubes in Steam Ge		5428	
 Total Heating Surface 	m²	7177	
 U-tube Outside Diameter 	mm	19.05	
 U-tube Thickness 	mm	1.09	
REACTOR CORE			
Equivalent Diameter	m	2.45	
Equivalent Height	m	3.66	
Equivalent Radial Thickness of t	he m	0.15	
Reflector			
• Equivalent Axial Thickness of th	ie m	0.10	
Reflector			
NUCLEAR FUEL Number of Fuel Assemblies		121	
	. I. <i>.</i>		
Number of Fuel Rods per Assemb	-	235	
Fuel Rod Array in Fuel Assembly		6 X 16	
Fuel Rod Length	m	3.658	
Clad Thickness	mm	0.572	
Clad Material	Z	IRLO™	
Fuel Chemical Composition			
Pellet Diameter	mm	8.192	
Pellet Height	mm	9.8	
Total Weight of Nuclear Fuel	t	48.7	

CONTROL RODS

Number of Control Rod Assemblies	;	33
Number of Absorber Rods per Asse	embly	20
Total Weight of Control Rod Assem	ibly kg	52.2
Neutron Absorber	Ag	g-In-Cd
Percentage Composition	%	80-15-5
Diameter	mm	8.36
Density	g/cm³	10.16
Clad Thickness	mm	0.445
Clad Material S	Steel SS	304

ENGINEERED SAFETY FEATURES

 Passive Safety Injection System 	/stem:	
No. of Pressure Vessels/	Accumulator Ta	inks 2
Volume of Each	m ³	36.4
Active Safety Injection Sys	stem:	
HP Safety Injection (SI)	Jern.	
		1
No. of Trains		4
No. of Pumps	_ /	2
Pump Flow Rate	m³/s	0.044
LP Safety Injection (RHI	२)	
No. of Trains		2
No. of Pumps		2
Pump Flow Rate	m³/s	0.14
Energency Core Cooling	Ś	40
Actuation Time	-	
/ letdation mile		
Τι	JRBINE GENE	RATOR
 Maximum Power 	MW	730
 Steam Flow Rate 	kg/s	1090
Fresh Steam Inlet Pressure	MPa	6.42
	(at)	(63)
• Fresh Steam Temperature	°C	. ,
Turbine Speed	rad/s	157
	(rotation/min)	
		(1500)

Steam Moisture at High-Pressu Turbine Inlet	re %	0.10
Condenser Pressure (Vacuum)	kPa	5.1
	(at)	(0.052)
Average Condensate Temperat	ure °C	33
Number of Feedwater Pumps		3
Feedwater Pump Capacity	%	50
Generator Rated Power	MVA	850
Rated Voltage	kV	21
Generator Rated Frequency	Hz	50
Cos fi	ø	0.876
Regulated Range	%	+5-5
RANSFORMERS		
Main Transformers:		
Rated Power	MVA	2 x 500
Voltage Ratio	kV	21/400
Load Tap Changing	%	+-10
Impedance Voltage	%	12.8/12.5
Unit Transformers:	70	12.07 12.0
Maximum Permissible	MVA	2 x 30
Continuous Power		
Voltage Ratio	kV	21/6.3
Impedance Voltage	%	10
Auxiliary Transformer:		
Maximum Permissible	MVA	60
Continuous Power		
Voltage Ratio	kV1	05/6.3/6.3
Load Tap Changing	%	+-15
Impedance Voltage	%	12

19

SIGNIFICANT DATES

December 1974

February 1975

20

September 1975 June 1976

- October 1976
- October 1977
- November 1979

- September 1981

- October 1980
- November 1980

May 1981

- October 1981

- February 1982
- July 1982

Erection works on Reactor Building finished. Start of Turbine Generator installation.

Plant.

Reka.

building site.

April 1978

- Fuel supplied.
 - Pressure and temperature nominal parameters achieved in the primary system.

First phase of test operation. Fuel inserted in the Reactor Vessel.

Foundation stone laid for Krško Nuclear Power

Start of Reactor Building erection.

Essential pressure tests completed.

Start of excavation and construction works on the

Arrival of the first nuclear equipment to the Port of

Both Steam Generators and Reactor Vessel installed.

- Self-sustaining chain reaction achieved in the reactor.
- Generator synchronised to the transmission line and the first kilowatts delivered to the Electric Utilities.
- 100% power achieved.
- Steam Generator Main Feedwater System modified.
- August 1982 Start of full-power operation.
- January 1983 Start of commercial operation.
 - July 1983 First yearly outage and refuelling.

Operating license issued by the Regulatory Body.

Plant Power Uprate and Full-Scope Simulator Construction.

Agreement between the Government of the Republic of Slovenia and the Government of the Republic of Croatia on regulating the status and other legal issues related to investments in the Krško Nuclear Power Plant, its utilisation and decommissioning.


Replacement of Low Pressure Turbines.

Replacement of Generator Stator.

Replacement of Reactor Head and Main Generator Rotor.

Connection of New Diesel Generator.

Reconstruction of Switchyard and Replacement of Main Transformer.





February 1984 May 2000

March 2003

April 2006 October 2010 April 2012

October 2013

April 2012

New Fuel Inspection

Temporary storage of Low and Intermediate Level Waste

07-0-0

pent Fuel Pit

Turbine Generator

-

Switchyard

Refuelling

Nuklearna elektrarna Krško -Krško Nuclear Power Plant Vrbina 12 8270 Krško Slovenia

> P: 00 386 7 48 02 000 F: 00 386 7 49 21 528 E-mail: nek@nek.si Website: www.nek.si

Publisher: Krško Nuclear Power Plant

Editors: Ida Novak Jerele Miran Pribožič

Edition: 1500 Issues

Issued: 2017

